







Elevations notes:
All tiled roofs to be repaired and extg tiles relaid.
All flashings repaired as required.
Extg cast iron rainwater goods to be repaired.
Missing gutters to be reinstated with cast iron half round gutters on rise and fall brackets.
Missing down pipes to be replaced with round cast iron pipes.
All rainwater goods to be painted light grey to match extg.

Cottage One
3 bedroom / 6 persons
Area = 127.40 m²

Cottage Two
2 bedroom / 4 persons
Area = 68 m²

N1 Existing timber shutter repaired and fastened open. New casement window within opening.

N2 Extg blocked up stone surrounded window reinstated with w20 steel framed casement.

N3 Form new opening with timber framed casement window.

N4 Existing shutter removed. New sliding sash window with timber infill below floor level.

N5 Window replaced with w20 steel framed casement within stone surround.

N6 Existing shutter removed. New casement window within opening.

N7 Window replaced with new timber framed casement window,pattern to match existing.

N8 Replace existing timber garage doors with timber clad timber framed construction to replicate doors with high level glazing to bedroom and bathroom.

N9 Retain extg door and fit new casement window with timber boarding below within extg opening.

N10 Form new opening with new half glazed stable door.

Latham architects

ST MICHAEL'S
QUEEN STREET
DERBY DE1 3SU
TEL:01332 365777
FAX:01332 290314
info@lathamarchitects.co.uk

ARCHITECTURE
CONSERVATION
PLANNING
LANDSCAPE
INTERIORS

creative reuse of land and buildings

PROJECT
MAYFIELD HALL

CLIENT
MR & MRS BRETT

SUBJECT
Conversion of existing outbuildings to holiday lets:
Cottages 1 and 2 proposed
plans and elevations

DRAWN Greenhatch /GR
CHECKED SH

NUMBER
2146B / P / 22
Revision
PLANNING APPLICATION

SCALE 1:100,1:200 @ A3
DATE NOV 2005

© This drawing and the building works depicted are the copyright of the architect and may not be reproduced except with written consent.
Written dimensions should be taken in preference to scaled dimensions.